

THE RIDGE COMPLEX PARCEL 3 KEYSTONE, COLORADO August 2020



**THE RIDGE COMPLEX
KEYSTONE, CO
COVER SHEET**

GENERAL NOTES

- The Contractor shall notify Alpine Engineering, Inc., and Developer at least 48 hours prior to any construction. The Contractor shall coordinate all work with Alpine Engineering, Inc. and Developer.
- Alpine Engineering, Inc., assumes no responsibility for utility locations. It is the Contractor's responsibility to field verify the location of all utilities prior to commencement of any construction.
- The Contractor shall conform to all Summit County rules, regulations and stipulations while accessing through or working in the County.
- The Contractor shall take all appropriate precautions to significantly reduce any potential pollution caused by his activities, including vehicle fueling, storage of fertilizers or chemicals, etc. The Contractor shall have identified procedures for handling potential pollutants and have identified spill prevention and response procedures prior to any activities at the project site.
- The Contractor shall keep 2 sets of contract drawings marked up to fully indicate asbuilt conditions. The drawings shall be provided to the Owner and Alpine Engineering, Inc. upon completion of this work. Contractor is to provide at least three ties from physical monuments to all fittings, valves, hydrants, curb stops, air vac valves, pr/s, manholes, and services.
- The Contractor shall maintain traffic at all times. The Contractor shall minimize traffic disruptions and provide adequate safety precautions to ensure public safety.
- Safety is the responsibility of the Contractor. The Engineer is not responsible for safety in, on, or about the project site, nor for compliance by the appropriate party with any regulations relating hereto.
- The Owner will designate staging areas.
- The Contractor shall minimize all off site tracking. All soil tracked off site shall be immediately cleaned up to the satisfaction of The Owner.
- If any groundwater is encountered the Contractor shall contact Developer, Alpine Engineering, Inc., and the Project Geotechnical Engineer immediately.
- The Contractor shall protect and preserve all trees, bushes, shrubs, and ground cover in a manner acceptable to the Owner.
- Observations of the work in progress and on-site visits are not to be construed as a guarantee or warranty by the Engineer of the Contractor's contractual responsibilities.
- All materials and workmanship shall be subject at inspection by the County and/or their representatives, and Alpine Engineering, Inc. The County reserves the right to accept or reject any such materials and workmanship that do not conform to the approved drawings and/or Summit County standards or specifications.
- Copies of county standards must be obtained by the Contractor. Contractor shall have one (1) copy of the plans and one (1) copy of the appropriate specifications on the job site at all times.
- Street closures shall be kept to a minimum length of time. There shall be no material storage on County Streets or property.
- Contractor shall conform to all recommendations in the subsoll study prepared by CTL Thompson (Report Project No. SU1381.000-120 dated July 25, 2017). Topographic information was provided by Range West Surveying.
- Contractor shall conform to the project technical specifications.



UTILITY NOTES

- The Contractor is warned that conflicts with existing utility services may exist. Prior to beginning any construction, the Contractor shall contact all appropriate utility companies for line locations. The Contractor shall then locate all utilities (including depth). Any conflicts with the proposed construction shall be brought to the attention of the Engineer so that line or grade changes can be made to eliminate any conflicts with these existing utilities. All existing utilities shall be protected from damage by the Contractor. Damaged utilities shall be repaired by the Contractor at no expense to the Owner.
- All construction activities and excavating for utility trenches shall meet OSHA requirements.
- PHONE: All phone conduits, pedestals, and appurtenances shall be installed in accordance with Centurylink's design specifications and shall be reviewed and accepted by Centurylink.
- CABLE TV: All cable tv conduits, pedestals, and appurtenances shall be installed in accordance with Centurylink's design specifications and shall be reviewed and accepted by Centurylink.
- All water mains and services shall have a minimum cover of 8.0 feet.
- Provide 10 feet minimum (clear) between all water and sewer, both mains and service lines, do not encase either.
- The Contractor shall mark all service line ends as shown on the details.
- The Contractor shall provide thrust blocks and megalug restraints at all bends and tees (c900 and DIP). Angles of water line bends are shown only as a guideline; all bends have not been identified or dimensioned, and additional bends may be required during construction.
- Water service lines may be Type K Copper up to 1" in size. The County recommends that SDR 9 NSF, flexible polyethylene, (Pure Core or similar) be used (this is required for services larger than 1"). A curb stop shall be installed for each service at the crestline or property line or edge of easement or as shown on the plans.
- The Contractor shall verify existing pipe or manhole inverts at tie in points prior to construction.
- The Contractor shall test all water mains in accordance with Town of Silverthorne standard specifications, tests to include pressure test, chlorine test, bacteria test and leakage test.
- The Contractor shall attend a mandatory preconstruction meeting with the Developer and Alpine Engineering, Inc., prior to the start of construction.
- All sewer pipe dimensions noted are inside edge of manhole to inside edge of manhole.
- All sewer lines shall have a minimum of 5 feet of cover, structural protection such as flowable fill with reinforcement may be required.
- Sewer service lines and all sewer mains must be SDR 26 PVC.
- Sewer acceptance. No air pressure test is required, vacuum test manholes, all sewer mains should be cleaned and televised prior to acceptance.
- The Contractor is responsible for coordinating, conducting and scheduling for the testing of all utilities and obtaining approval and acceptance from all utilities.
- The Contractor may need to perform hydraulic testing and disinfection of existing waterlines as part of the testing and acceptance procedure for the proposed waterline.
- Compaction of all trenches and bedding must be attained as per specifications.

GRADING AND DRAINAGE NOTES

- All work performed for this project including storm drains and culverts shall be constructed in accordance with Summit County standards and the project Technical Specifications.
- All drain pipes shall be installed with the required bedding.
- Elevations shown are at pipe invert unless otherwise shown.
- All standard storm drain structures are subject to modification by the Engineer to meet field requirements.
- Where any part of the storm drain system is located in a fill section, provide fill material compacted to 95% AASHTO T99 density from the original undisturbed ground up to structure bottom slabs and pipe bedding.
- Inlet boxes to be oversized to accommodate pipe size where necessary. Provide traffic load rated inlet box and top slab to accommodate grate and frame for oversized boxes.
- Pipe lengths indicated are slope lengths measured along the centerline of pipe from inside face of box to inside face of box.
- Curb and Gutters shall be installed in such a manner as to insure positive drainage in all areas, as shown.
- Direct downspout drainage away from building foundation or to storm per Geotechnical Engineer.
- Ditch revegetation and ditch protective linings will require field adjustment during construction to account for varying soil conditions. Revegetation and linings will be evaluated after ditches are constructed.
- Grading adjacent to buildings shall be at a slope away from the building of 1' in 10' per the geotechnical report.
- The Contractor shall maintain existing drainage channels, culverts, and appurtenances during construction as necessary to protect roads and property.
- The Contractor shall remove all topsoil and man placed fill prior to commencement of construction.
- The ground surface surrounding the exterior of buildings shall be graded to slope away from the foundations in all directions.
- Proof roll all hardscape areas prior to installing basecourse and pavement, per Geotechnical Report.

XCEL ENERGY NOTES

- TRENCH AND CONDUIT**
 - The developer or contractor will contact Xcel Energy before conduit and vault installation begins to schedule a pre-construction meeting with the project inspector.
 - Changes in power facility construction from that shown on the project plans will not be made without advance approval from the Xcel Energy inspector.
 - Xcel Energy material shall not be moved from the project to which it was assigned without the advance approval of the inspector and the completion of necessary paperwork. Xcel Energy material shall not be installed for any use other than construction of power facilities.
 - All roads will be built to subgrade and all drainages will be constructed to grade before any vaults or conduits are installed.
 - All electric primary trench will be excavated deep enough to ensure that the top of installed power facilities will be 30" below final grade. Special care must be taken to insure that the top of conduits will be 30" below the bottom of drainage ditches and all other low areas. Gas shall be buried at 24" min.
 - Trench will be as straight as possible between vaults and shall have a smooth bottom free from low and high spots. Six inches of road base will be placed the entire length of the trench and well compacted prior to conduit installation. When placed in the trench, the conduit shall be in continuous contact with the compacted road base with no hold down weight added. Twelve inches of road base, as measured from the top of the conduit, will be placed on the conduit and well compacted prior to returning any native backfill to the trench. Large rocks shall not be placed directly on the road base layer. Care must be taken to avoid conduit damage during backfill and compaction; conduits found to be unusable at the time of power cable installation will be repaired by the developer or contractor before power can be made available.
 - Power facilities to be placed parallel to deeper utilities will have a horizontal separation from the deeper utility greater than the depth of such utility below final grade less four feet. When crossing a deeper utility is unavoidable, the crossing will be made as close to perpendicular as possible.
 - The conduit will not be backfilled without the Xcel Energy inspector seeing all joints unless the inspector gives prior permission. All joints shall be completely sealed to the line marked on the male end of the conduit after sufficient glue is applied to both conduits being jointed, even in areas where the trench cannot be excavated completely straight. Glue in the joint shall be allowed to completely dry prior to any stress being applied to the conduit on either side of the joint. Trench backfilled without the inspector viewing each joint or giving prior permission to cover the conduit will be re-excavated to expose the conduit, or the contractor will put a camera through each conduit in the span which was prematurely backfilled to verify the joint sealing and conduit condition. The camera verification will be witnessed by the Xcel Energy inspector.
 - Individual conduits shall enter each vault at a consistent location. There is to be no crossing of conduits in the trench. Pull string shall be installed in all conduit.
 - Both ends of a conduit run shall be securely plugged at the time of installation with Xcel Energy supplied material. Conduit ending outside a vault shall be marked with a 4" x 4" post or other approved method.
 - Red trench marking tape will be supplied by Xcel Energy and shall be installed 18" to 24" above the conduit during backfill.
- VAULTS**
 - Vaults shall be installed as follows:
 - Splice vaults shall be installed with the manhole lid grade being slightly above final grade of the surrounding area, except when the vault is in a roadway, the manhole lid grade shall match the grade of the finished roadway surface.
 - Transformer vaults and switchgear vaults will be installed with the bottom of the lid at final grade. The lid will be level.
 - Holes knocked in vaults for conduit installation shall be as small as possible and shall be grouted closed on the outside of the vault prior to backfill.
 - Conduit shall enter vaults perpendicular to the vault wall.
 - Conduit will extend 4" into the vault (measured from the inside wall of the vault) after backfilling is complete.
 - After the vault has been set, pipes extended in and grouted and the ground rod is in place, vaults shall be swept out removing all dirt or rocks. Cleanup shall be completed to the satisfaction of the inspector prior to cable installation being scheduled.
 - Pedestals for other utilities shall not be located closer than 10' to a vault on sides where transformers or switchgear will have access doors. Pedestals shall not be located closer than 5' to a vault on sides where the pad-mounted equipment will not have access doors.

SHEET INDEX

COVER SHEET	C1.0
EXISTING CONDITIONS	N/A
GEOMETRIC SITE LAYOUT PLAN	C1.1
GRADING PLAN & PROFILES	C2.0
STORM DRAINAGE PLAN	C3.0
WATER AND SEWER PLAN & PROFILES	C4.0
SHALLOW UTILITY PLAN	C5.0
EROSION CONTROL PLAN	C6.0
DETAILS	C7.0-C7.1

PROJECT CONTACTS

DEVELOPER, BUCKHEAD RENOVATIONS	MICHAEL O'SULLIVAN	(404)229-0676
ARCHITECT	TODD WEBBER	(970)668-9402
CIVIL ENGINEER, ALPINE ENGINEERING, INC.	MATT WADEY	(970)926-3373
GEOTECH, CTL THOMPSON, INC.	GEORGE BENECKE	(970)453-2047
LAND SURVEYOR, RANGE WEST, INC.	ROBERT JOHNS	(970)468-6281
WATER, WATER WORKS WEST	RON MENTCH	(970)468-7480
SEWER, SNAKE RIVER SANITATION	STONER TURNER	(970)468-8794
ELECTRIC & GAS, XCEL ENERGY	NANCY HOWARD	(970)262-4050
CABLE TV, COMCAST	TONY HILDRETH	(970)401-2782
TELEPHONE, CENTURYLINK	KIRK CLAPP	(970)468-6860


NO.	DATE	REVISIONS	BY	
			MCW	MCW
1	1/29/2019	PRELIMINARY PLAN SUBMITTAL	MCW	
2	08/09/2019	PRELIMINARY PLAN RESUBMITTAL	MCW	
3	06/15/2020	PLAN RESUBMITTAL	MCW	
DESIGNED	MCW			
DRAWN	MCW			
CHECKED	GLB			
JOB NO.	xxx			
DATE	10/18/2018			

**SHEET
C1.0**

SNAKE RIVER TRACT C
OPEN SPACE

LEGEND


- PROPERTY LINE
- EASEMENT
- PROPOSED BOULDER RETAINING
- PROPOSED CONCRETE/ASPHALT



ALPINE ENGINEERING INC.
34510 HWY 6 / UNIT A9 / P.O. BOX 97
EDWARDS CO. BRIDGE / 70026-0373
WWW.ALPIENGINEERING.COM



THE RIDGE COMPLEX
KEYSTONE, CO
GEOMETRIC SITE LAYOUT



NO.	DATE	REVISIONS	BY
1	1/29/2019	PRELIMINARY PLAN SUBMITTAL	MCW
2	09/09/2019	PRELIMINARY PLAN RESUBMITTAL	MCW
3	06/15/2020	PLAN RESUBMITTAL	MCW

DESIGNED	MCW	DATE	10/18/2018
DRAWN	MCW		
CHECKED	GLB		
JOB NO.	xxx		


SHEET C1.1

C:\Keystone\Seasons at Keystone\Dwg\MasterSite Layout.dwg, 6/15/2020 1:15:46 PM, waddy

SNAKE RIVER

LEGEND

	PROPERTY LINE
	EXISTING CONTOUR
	EASEMENT
	PROPOSED CONTOUR
	PROPOSED GRADING, SLOPE/SPOT
	EXISTING GRADING, SLOPE/SPOT
	PROPOSED STORM SEWER
	PROPOSED BOULDER RETAINING
	PROPOSED CONCRETE/ASPHALT




TOPOGRAPHIC INFORMATION
PROVIDED BY RANGE WEST
SURVEYING

ALPINE ENGINEERING INC.
34510 HWY 6 UNIT A9 P.O. BOX 97
EDWARDS CO 81622-7402/263073
WWW.ALPIENGINEERING.COM



THE RIDGE COMPLEX KEYSTONE, CO GRADING PLAN



NO.	DATE	REVISIONS	BY
1	1/29/2019	PRELIMINARY PLAN SUBMITTAL	MCW
2	08/09/2019	PRELIMINARY PLAN RESUBMITTAL	MCW
3	06/15/2020	PLAN RESUBMITTAL	MCW

DESIGNED	MCW
DRAWN	MCW
CHECKED	GLB
JOB NO.	xxx
DATE	10/18/2018

**SHEET
C2.0**

C:\Keystone\Seasons at Keystone\DWG\MasterGrading.dwg, 8/13/2020 4:26:56 PM, wadey

SNAKE RIVER

LEGEND

- PROPERTY LINE
- EXISTING CONTOUR
- EASEMENT
- PROPOSED CONTOUR
- PROPOSED GRADING, SLOPE/SPOT
- EXISTING GRADING, SLOPE/SPOT
- PROPOSED STORM SEWER
- PROPOSED BOULDER RETAINING
- PROPOSED CONCRETE/ASPHALT



GRAPHIC SCALE
 (IN FEET)
 1 inch = 20 ft.

TOPOGRAPHIC INFORMATION
 PROVIDED BY RANGE WEST
 SURVEYING

ALPINE ENGINEERING INC.
 34510 HWY 6 UNIT A9 P.O. BOX 97
 EDWARDS CO 81622 / 970.296.3373
 WWW.ALPECIVIL.COM

COLORADO LICENSED
 PROFESSIONAL ENGINEER
 #39865

THE RIDGE COMPLEX KEYSTONE, CO STORM DRAINAGE PLAN



NO.	DATE	REVISIONS	BY
1	1/29/2019	PRELIMINARY PLAN SUBMITTAL	MCW
2	05/09/2019	PRELIMINARY PLAN RESUBMITTAL	MCW
3	05/15/2020	PLAN RESUBMITTAL	MCW

DESIGNED	MCW
DRAWN	MCW
CHECKED	GLB
JOB NO.	xxx
DATE	10/18/2018

SHEET
 C3.0

C:\Keystone\Seasons at Keystone\DWG\Master\Storm.dwg, 6/15/2020 1:16:31 PM, wexley

SNAKE RIVER

TOPOGRAPHIC INFORMATION PROVIDED BY RANGE WEST SURVEYING

TOPOGRAPHIC INFORMATION PROVIDED BY RANGE WEST SURVEYING


ALL WATER MAINS FITTINGS TO BE RESTRAINED WITH MEGALUGS AND CONCRETE THRUST BLOCKS

ALL WATER SERVICES TO BE SIZED BY PLUMBER AND FIRE PROTECTION CONSULTANT


SEE SNAKE RIVER WATER AND SEWER SYSTEM STANDARDS AND SPECIFICATIONS

LEGEND	
PE	PROPOSED ELECTRIC
PES	PROPOSED ELECTRIC SERVICE
PCL	PROPOSED CENTURYLINK
PCOM	PROPOSED COMCAST
PGS	PROPOSED GAS SERVICE
8" DIP	PROPOSED WATER
8" PVC	PROPOSED SEWER
6" DIP	PROPOSED FIRE HYDRANT W/V
[Symbol]	PROPOSED TRANSFORMER & COMM. PEDESTAL
EE	EXISTING ELECTRIC
EG	EXISTING GAS
EP	EXISTING PHONE
S	EXISTING SEWER
EW	EXISTING WATER
IRR	EXISTING IRRIGATION
[Symbol]	EXISTING TELEPHONE PEDESTAL
[Symbol]	EXISTING ELECTRIC VAULT
[Symbol]	EXISTING SEWER MANHOLE
[Symbol]	EXISTING WATER VALVE
---	PROPERTY LINE


ALPINE ENGINEERING INC.
 34510 HWY 6 UNIT A9 P.O. BOX 97
 EDWARDS CO. BR22 / 70702623073
 WWW.ALPIENGINEERING.COM



THE RIDGE COMPLEX KEYSTONE, CO WATER & SEWER PLAN



PROFILE: 8" SEWER MAIN SCALE: VERT. 1"=20' HORIZ. 1"=20'



NO.	DATE	REVISIONS	BY
1	1/29/2019	PRELIMINARY PLAN SUBMITTAL	MCW
2	05/09/2019	PRELIMINARY PLAN RESUBMITTAL	MCW
3	06/15/2020	PLAN RESUBMITTAL	MCW


DESIGNED	MCW
DRAWN	MCW
CHECKED	GLB
JOB NO.	xxx
DATE	10/18/2018

SHEET C4.0


© KeystoneSeasons at KeystoneDwgMasterUtility.dwg, 6/15/2020 1:17:21 PM, wadley

TOPOGRAPHIC INFORMATION
PROVIDED BY RANGE WEST
SURVEYING

LEGEND	
PE	PROPOSED ELECTRIC
PES	PROPOSED ELECTRIC SERVICE
PCL	PROPOSED CENTURYLINK
PCOM	PROPOSED COMCAST
PGS	PROPOSED GAS SERVICE
8" DIP	PROPOSED WATER
8" PVC	PROPOSED SEWER
6" DIP	PROPOSED FIRE HYDRANT W/GV
T	PROPOSED TRANSFORMER & COMM. PEDESTAL
EE	EXISTING ELECTRIC
EG	EXISTING GAS
EP	EXISTING PHONE
S	EXISTING SEWER
EW	EXISTING WATER
IRR	EXISTING IRRIGATION
T	EXISTING TELEPHONE PEDESTAL
V	EXISTING ELECTRIC VAULT
M	EXISTING SEWER MANHOLE
V	EXISTING WATER VALVE
- - -	PROPERTY LINE



SNAKE RIVER



ALPINE
ENGINEERING INC.
34510 HWY 6 UNIT A9 IPO BOX 97
EDWARDS CO BR52 7602823073
WWW.ALPIENGINEERING.COM




THE RIDGE COMPLEX
KEYSTONE, CO
SHALLOW UTILITY PLAN

NO.	DATE	REVISIONS	BY
1	1/29/2019	PRELIMINARY PLAN SUBMITTAL	MCW
2	08/09/2019	PRELIMINARY PLAN RESUBMITTAL	MCW
3	06/15/2020	PLAN RESUBMITTAL	MCW

DESIGNED	MCW
DRAWN	MCW
CHECKED	GLB
JOB NO.	xxx
DATE	10/18/2018

SHEET
C5.0

C:\Keystone\Seasons at Keystone\DWG\Master\Shallows.dwg, 01/15/2020 11:52:03 PM, wexley



CONSTRUCTION SEQUENCE OF EROSION/SEDIMENT CONTROL MEASURES

- BEFORE COMMENCING GRADING OR CONSTRUCTION
1. CONSTRUCT STABILIZED CONSTRUCTION ENTRANCES AT ALL POINTS OF INGRESS AND EGRESS.
 2. CONTRACTOR SHALL TAKE APPROPRIATE MEASURES TO ASSURE THAT NO SEDIMENT LEAVES THE SITE.
 3. CONSTRUCT SILT FENCE AND WATTLES AND ALL SEDIMENT CONTROL DEVICES.
 4. BEGIN DEMOLITION, EXCAVATION AND CONSTRUCTION.
 5. INSTALL EROSION CONTROL MEASURES AFTER DITCHES AND SWALES HAVE BEEN CONSTRUCTED AND TOPSOIL AND SEED HAVE BEEN PLACED. INSTALL INLET PROTECTION IN ALL INLETS AS THEY ARE CONSTRUCTED.
 6. TOPSOIL AND REVEGETATE ALL DISTURBED AREAS WITH APPROVED SEED MIX PER LANDSCAPE PLAN.
 7. CONTRACTOR SHALL REMOVE SEDIMENT CONTROL FACILITIES AFTER FINAL STABILIZATION.

FUGITIVE DUST CONTROL

THE CONTRACTOR IS RESPONSIBLE TO CONTROL FUGITIVE DUST AND TO INCORPORATE THE FOLLOWING:


1. ALL UNPAVED ROADS AND OTHER DISTURBED AREAS ON SITE SHALL BE WATERED TO MINIMIZE FUGITIVE DUST.
2. HAUL ROADS SHALL BE TREATED WITH MAGNESIUM CHLORIDE IF WATER IS NOT CONTROLLING THE DUST.
3. ALL DISTURBED SURFACE AREAS SHALL BE REVEGETATED OR SURFACED PER THE LANDSCAPE PLAN AS SOON AS POSSIBLE.
4. MUD AND DIRT CARRYOUT ONTO PAVED SURFACES SHALL BE PREVENTED. ANY MUD AND DIRT CARRYOUT ONTO PAVED SURFACES SHALL BE CLEANED UP DAILY.

GENERAL NOTES FOR SEDIMENT CONTROL


1. CONTRACTOR SHALL SUBMIT A CONSTRUCTION STAGING & MANAGEMENT PLAN IDENTIFYING CONSTRUCTION FENCING, STAGING, STORAGE & CONSTRUCTION TRAILER LOCATION PRIOR TO COMMENCEMENT OF CONSTRUCTION ACTIVITIES.
2. INSTALL AND MAINTAIN SEDIMENT CONTROL MEASURES IN ACCORDANCE WITH THESE PLANS AND AS NEEDED TO PREVENT SEDIMENT FROM DISCHARGING OFF-SITE OR ENTERING THE RIVER.
3. ALL PROPOSED SEDIMENT CONTROL MEASURES ARE TEMPORARY MEASURES UNLESS SPECIFIED OTHERWISE ON PLANS.
4. SEDIMENT CONTROL MEASURES MAY REQUIRE FIELD ADJUSTMENTS AT THE TIME OF CONSTRUCTION TO INSURE THAT THEIR INTENDED PURPOSE IS ACCOMPLISHED.
5. PROVIDE REGULAR INSPECTION AND MAINTENANCE OF ALL SEDIMENT CONTROL MEASURES TO INSURE THAT SEDIMENT CONTROL EFFICIENCY IS OBTAINED UNTIL FINAL STABILIZATION OF SITE HAS TAKEN PLACE.
6. INSTALL SEDIMENT CONTROL MEASURES AT THE ONSET OF GRADING OPERATIONS SO THAT EFFECTIVE SEDIMENT CONTROL CAN BE ACHIEVED DURING THE ENTIRE CONSTRUCTION PERIOD.
7. STABILIZE ALL POINTS OF INGRESS AND EGRESS WITH TRACKING PAD DURING CONSTRUCTION TO PREVENT TRACKING OF MUD ONTO PUBLIC WAYS.
8. FOR TEMPORARY STOCKPILES APPLY SEED, HYDROMULCH AND TACKIFIER IMMEDIATELY AFTER THEY ARE CONSTRUCTED FOR STABILIZATION. IF EROSION OCCURS AFTER APPLICATION OF THE TACKIFIER, USE EXCELSIOR C2 EROSION CONTROL FABRIC. INSTALL SILT FENCE BELOW STOCKPILES TO CAPTURE SEDIMENT.
9. THE TERM 'REVEGETATION' ON THIS PLAN MEANS THE SUCCESSFUL GERMINATION AND ESTABLISHMENT OF STABLE GRASS COVER FROM A PROPERLY PREPARED SEEDBED CONTAINING THE SPECIFIED AMOUNTS OF FERTILIZER IN ACCORDANCE WITH APPLICABLE 'STANDARDS AND SPECIFICATIONS'. REFER TO LANDSCAPE PLANS FOR SEED MIX, FERTILIZER TYPE, MULCH, TACKIFIER AND APPLICATION RATES.
10. IT IS THE CONTRACTOR'S RESPONSIBILITY TO TAKE APPROPRIATE MEASURES TO INSURE THAT NO SEDIMENT LADEN WATER IS DISCHARGED FROM THE SITE.
11. APPROVAL SHALL BE REQUESTED UPON FINAL STABILIZATION OF ALL SITES BEFORE REMOVAL OF SEDIMENT CONTROLS.
12. CONTRACTOR SHALL OBTAIN AND CONFORM TO STORMWATER DISCHARGE PERMIT AND ALL ENVIRONMENTAL PERMITS AND KEEP STREETS CLEAN AND FREE OF SEDIMENT.
13. REMOVAL AND CLEANUP OF ANY SEDIMENT THAT LEAVES THE SITE IS THE RESPONSIBILITY OF THE CONTRACTOR.

LEGEND

- EROSION LOG WATTLES
- SILT FENCE
- STABILIZED CONSTRUCTION ENTRANCE
- SILT SACK INLET PROTECTION
- DITCH EROSION LOG



TOPOGRAPHIC INFORMATION PROVIDED BY RANGE WEST SURVEYING




THE RIDGE COMPLEX
KEYSTONE, CO
EROSION CONTROL PLAN

NO.	DATE	REVISIONS	BY
1	1/29/2018	PRELIMINARY PLAN SUBMITTAL	MCW
2	05/09/2019	PRELIMINARY PLAN RESUBMITTAL	MCW
3	06/15/2020	PLAN RESUBMITTAL	MCW


DESIGNED	MCW
DRAWN	MCW
CHECKED	GLB
JOB NO.	xxx
DATE	10/18/2018

SHEET C6.0


© Keystone/Seasons at Keystone/Dwg/Master/Erosion.dwg, 6/15/2020 11:24:47 PM, wadley



N.T.S.



N.T.S.




N.T.S.


A ASPHALT SECTIONS

B CONCRETE DUMPSTER PAD SECTION


C BOULDER WALL



N.T.S.



N.T.S.




N.T.S.


D ROAD CUT DETAIL

E CONCRETE JOINTING


F CULVERT BEDDING






N.T.S.




N.T.S.




N.T.S.



I ELEC./PHONE TRENCH



J GAS TRENCH



K DOWNSPOUT CONNECTION

NO.	DATE	REVISIONS	BY
1	10/18/2018	PRELIMINARY PLAN SUBMITTAL	MCW
2	09/09/2019	PRELIMINARY PLAN RESUBMITTAL	MCW
3	06/15/2020	PLAN RESUBMITTAL	MCW

DESIGNED RIF	DRAWN RIF	CHECKED MCW	JOB NO. XXX	DATE 10/18/2018

